

GROUND CONTROL STATION GCS.A

The GCS.A unmanned systems command center provides everything required for operators to undertake missions in complete comfort and safety, including climate control, redundant power and communications.

State-of-the-art features and amenities include:

- Autonomous operating time up to 48 hours
- Housing for the communication and control equipment
- Three workplaces for the pilots and the payload operators
- Directional antenna for telemetry and communication
- Directional antenna for video and data links
- Support Equipment for the unmanned aerial system (transport module)



The GCS.A is installed into a modified 20-foot container, enhanced with a generator section.

www.uavos.com
uavos@uavos.com



SPECIFICATIONS

PARAMETER	DATA
Operating temperature	-40°F to +131°F (-40°C to +55°C)
Automated workplaces	2+1
Dimensions	Length 295 in (7500 mm), width 98 in (2492 mm), height 102 in (2585 mm)
Transportation	truck tractor
Generator	15 kW
Autonomous operating time	48 h



Customization:

- Power Options
- Comfort Options
- Computer Options
- Utility Options
- Safety Options

www.uavos.com
uavos@uavos.com

